

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20711-00-01
Spot: SENWNENE Sec/Twnshp/Rge: 13-19S-9W
4627 feet from S Section Line, 737 feet from E Section Line
Lease Name: KOENIG Well #: 1-13
County: RICE Total Vertical Depth: 2535 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST. PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2400		
PROD	5.5	2523	1712	100 SX
SURF	8.625	222		150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/01/2016 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-0895

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 02/01/2016 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2257' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 1712' AND PULL TO 1200' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC, PULL CASING TO 800', WAIT 1 HOUR AND TAGGED CEMENT AT 1050' WITH SWAB BAR. PUMP 35 SX'S AT 800', PULL CASING TO 270' AND CIRCULATE 60-40 POZ, 4% GEL CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2330	2354		CSG

Received
KANSAS CORPORATION COMMISSION
FEB 11 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND TICKET #C-43662. DENIED TA

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)