

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-02891-00-03
Spot: SESWNENE Sec/Twnshp/Rge: 15-9S-21W
1308 feet from N Section Line, 973 feet from E Section Line
Lease Name: MOREL A Well #: 1
County: GRAHAM Total Vertical Depth: 3720 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3695		
COND	16	207		175 sx
PROD	7	3712		300 SX
SURF	9.625	1479		600 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2016 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: NEIL PFANNENTIEL Company: EXPRESS WELL SERVICE & SUPPL Phone: (281) 891-1000

Proposed Plugging Method: Ordered 625 sx 60/40 pozmix 4% gel cement, 100 sx common cement w/3% cc, 400 # hulls and 23 sx gel.
Perforations: 3371' - 3378', 3407' - 3622', 3712' - 3720'.
Method: CIBP: 3695'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2016 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 1450'.
Ran tubing to 3123' and pumped 150 sx common cement w/3% cc. Pulled tubing to 2700'. Let cement set for one hour. Tubing plugged up. Pulled all tubing out. Found 12 joints of tubing full of cement. Ran tubing back to 2310' and pumped 17 sx gel followed by 15 sx cement and cleared tubing. Pulled tubing to 1450' and pumped 380 sx cement w/100 # hulls. Good circulation of cement. Pulled tubing. Tied on to casing and squeezed w/35 sx cement. Shut in pressure 300 psi. Tied on to backside and squeezed w/15 sx cement. Shut in pressure 100 psi.

GPS: 39.27453 -099.64590

Perfs:

Top	Bot	Thru	Comments
3712	3720		
3407	3622		
3371	3378		


Received
KANSAS CORPORATION COMMISSION
FEB 19 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING TICKET # 67725

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM