

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21026-00-00
Spot: NWSENWSW Sec/Twnshp/Rge: 16-26S-8E
1842 feet from S Section Line, 4298 feet from E Section Line
Lease Name: LARCOMA Well #: 1
County: BUTLER Total Vertical Depth: 2575 feet

Operator License No.: 32701
Op Name: C & G DRILLING, INC.
Address: 701 E. RIVER ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2564		150 SX
SURF	7	107		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2016 12:00 PM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: TIM GULICK Company: C&G DRILLING Phone: (620) 583-4306

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 02/02/2016 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1/29/2016 1) RAN TUBING IN TO 2562' AND SPOT 30 SKS OF CLASS A CEMENT W/3% CACL. 2) PULL UP 17 JOINTS, RAN IN WIRELINE AND TAGGED PLUG AT 2211'. 3) PULLED TUBING OUT OF HOLE AND RAN IN ON WIRELINE TO PERFORATE AT 250'. 4) RAN IN WITH TUBING TO 270' AND PUMPED 70 SKS OF 60/40 4% CEMENT (NO ADDITIVES). CEMENT CIRCUALTED UP 4.5" CASING AND BACKSIDE TO SURFACE. 2/1/2016. SURFACE CEMENT FELL BACK > 100'. 2/2/2016 TOPPED OFF W/ 15 SKS CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2564	2575	OH	

Remarks: CEMENTING COMPLETED BY ELITE CEMENTING, EUREKA, KS. TICKET #2696. PLUGGED DUE TO COMPLIANCE W/ 82-3-111.

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

220
2-26-16