

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-40260-00-00  
Spot: NENWSWSE Sec/Twnshp/Rge: 18-26S-6E  
991 feet from S Section Line, 2056 feet from E Section Line  
Lease Name: FALKENBERG Well #: 4  
County: BUTLER Total Vertical Depth: 2717 feet

Operator License No.: 6655  
Op Name: CRAWFORD, GARRY F. DBA CRAWFO  
Address: PO BOX 727  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2643		
PROD	7	2693		30 SX
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2015 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: BRANCE CRAWFORD Company: CRAWFORD PRODUCTION CO. Phone: (316) 323-5513

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2640' W/4SXS CIRC. 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/22/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2650', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. TAGGED CEMENT @ 2390'. PRESSURED CASING @ 200#, HELD OK. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 250'-251'. WELL WOULD NOT CIRCULATE, PUMPED 130 BBLs W/LOST CIRCULATION MATERIAL. SWEDGED INTO CASING, CONSOLIDATED MIXED & PUMPED 50 SXS CLASS A COMMON & DISPLACED @ 300'. WAITED 2 HOURS, WELL WOULD NOT CIRCULATE. CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 100 MSXS CLASS A COMMON & DISPLACED @ 300'. SDON. WELL CIRCULATED, CONSOLIDATED MIXED & PUMPED 237 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #51157, & 51134.

Perfs:

Top	Bot	Thru	Comments
2693	2717	OH	

Received  
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE / 10 YR RULE - DENIED TA

Plugged through: TBG

FEB 11 2016

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

no  
2-26-16

✓