

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-40258-00-00  
Spot: NESENESE Sec/Twnshp/Rge: 5-27S-6E  
1665 feet from S Section Line, 312 feet from E Section Line  
Lease Name: BEADLES Well #: W-2  
County: BUTLER Total Vertical Depth: 3155 feet

Operator License No.: 6655  
Op Name: CRAWFORD, GARRY F. DBA CRAWFO  
Address: PO BOX 727  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3155		125 SX
SURF	8.625	211		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/01/2016 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: BRANCE CRAWFORD Company: CRAWFORD PRODUCTION CO. Phone: (316) 323-5513

Proposed Plugging Method: AS PER KCC RULES & REGS / BOTTOM PLUG ,CIRC. FROM 250'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE  
Date/Time Plugging Completed: 02/01/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH / W/ TBG @ 3,145', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. TAGGED CEMENT @ 2,655'. RIH W/TBG @ 260', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #51149.

Perfs:

Top	Bot	Thru	Comments
3139	3145		CSG

Received  
KANSAS CORPORATION COMMISSION  
FEB 11 2016  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: CEMENT @ SURFACE ON BACKSIDE OF PRODUCTION CASING/ COMPLIANCE / 10 YEAR RULE - DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)