

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-40220-00-00  
Spot: NWSEW Sec/Twnshp/Rge: 31-24S-4E  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: MCGILL Well #: 9  
County: BUTLER Total Vertical Depth: 2684 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION DBA A  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2675		0 SX
SURF	12.5	210		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2015 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: STEVEN KILE Company: BUCKEYE/AZTEC Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/23/2015 3:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) OLD, INACTIVE WELL - TUBING & RODS PARTED WHEN BEING PULLED. 2) PULLED 580' TUBING OUT AND 530' OF RODS. 3) WENT IN TO FISH RODS, RECOVERED ADDITIONAL 23 RODS (DOWN TO APPROX. 725'). 4) RAN IN HOLE W/ OVERSHOT TO FISH REMAINING TUBING, OUTSIDE OF CASING AT APPROX 750' (OVER SHOT PACKED WITH MUD). PULLED OUT. 5) RAN IN HOLE W/ BIT, ONLY ABLE TO GO DOWN TO 485'. PULLED OUT. 6) RAN IN HOLE W/ 470' OF TUBING, PUMPED 331 SKS OF 60/40 4% CEMENT. CIRCUALTED CEMENT UP 5.5" CASING. BACKSIDE CIRCUALTED FLUID. 7) RAN DOWN BACKSIDE OF 5.5" CASING W/ 1" TO 260', CIRCUALTED 71 SKS OF CEMENT. 8) TOPPED OFF WITH ADDITIONAL 45 SKS CEMENT. 9) PIPE CUT DOWN BELOW SURFACE AND BURIED. VERIFIED CEMENT AT SURFACE ON 11/24/2015.

Perfs:

Top	Bot	Thru	Comments
2675	2684	OH	

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES, EL DORADO, KS. TICKET #48410.

Plugged through: TBG

District: 02

Signed Jonathan Hill  
(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

2-26-16