

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-20946-00-01  
Spot: SENWSWSW Sec/Twnshp/Rge: 21-26S-7E  
782 feet from S Section Line, 4777 feet from E Section Line  
Lease Name: HENN Well #: 2  
County: BUTLER Total Vertical Depth: 2860 feet

Operator License No.: 7228  
Op Name: BRICKLEY, DONALD DBA D & J INVES  
Address: 107 SE BLUESTEM RD. PO BOX 107  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2856		75 SX
SURF	8.62	200		75 SX
SURF		204		

Well Type: EOR UIC Docket No: E19324.1 Date/Time to Plug: 10/14/2015 8:00 AM  
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL  
Proposal Rcvd. from: ANDY BRICKLEY Company: D & J INVESTMENTS Phone: (316) 323-4623

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 2790 W/4 SXS CEMENT, CIRC 250'-0'.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/14/2015 8:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, TAGGED TD @ 2846', POOH W/WIRELINE. SANDED BACK WELL BACK @ 2790'. SDON. 10/15/2015, DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. 10/19/2015, RIH ON WIRELINE, CUT CASING @ 600', LAYED DOWN 600' 4 1/2" CASING. RIH W/ 4 1/2" DUMP BAILOR & BAILED HOLE @ 250', CNC POURED 5 1/2 YDS (110 SXS) OIL SLURRY LESS 10% SAND TO SURFACE. P&A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2840	2850		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

*Handwritten:* No 2-26-16 CC-UIC

*Handwritten:* ✓