

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-02346-00-00
Spot: SWNW Sec/Twnshp/Rge: 6-11S-20W
4058 feet from S Section Line, 4379 feet from E Section Line
Lease Name: BIEKER LEASE Well #: 5
County: ELLIS Total Vertical Depth: 3708 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3710		125 SX
SURF	8.625	208		150 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/09/2016 10:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: CURT GABEL

Company: BEREXCO LLC

Phone: (785) 628-6101

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.
Removed retrievable plug.
Perforations: 3628' - 3634', 3637' - 3639' and 3642' - 3648'

Plugging Proposal Received By: PAT STAAB

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/09/2016 2:30 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 2250', 1509' and 790'. Berexco ran in hole with tubing to 3500'. Pumped 10 sx gel followed by 75 sx cement w/300 # hulls mixed in. Pulled tubing to 1750' and pumped 170 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2' casing w/20 sx cement. Hole standing full. Rigged to 8 5/8' surface casing and pumped 5 sx cement w/200 psi. Shut in pressure 200 psi.

GPS: 39.12816 -099.58921

Perfs: -

Top	Bot	Thru	Comments
3642	3648		
3637	3639		
3628	3634		

Received
KANSAS CORPORATION COMMISSION

FEB 19 2016

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING TICKET # 1509

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

No
2-26-16