

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-02705-00-00
Spot: SWSESWNE Sec/Twnshp/Rge: 35-20S-9W
2952 feet from S Section Line, 1702 feet from E Section Line
Lease Name: TOBIAS SIMPSON UNIT Well #: 4-9
County: RICE Total Vertical Depth: 3381 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3300		
PROD	5.5	3381		100 SX
SURF	8.625	203		175 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/16/2016 10:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: DENNIS KIRMER

Company: BEREXCO, LLC.

Phone: (316) 772-6449

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK

WitnessType: PARTIAL

Date/Time Plugging Completed: 02/17/2016 11:30 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, CK BOTTOM. PERFORATE AT 1200', 750', AND 250'. RUN TUBING TO 3280' AND PUMP 10 SX'S CEMENT ON TOP OF CIBP. PULL UP 4 JTS TUBING AND PUMP GEL UP TO 1200'. PULL TUBING ON UP TO 1200' AND PUMP 35 SX'S COMMON CEMENT WITH 2% CC AND 100# COTTON HULLS. PULL TUBING ON OUT AND WAIT 1.5 HOURS. ATTEMPT TO TAG CEMENT, COULDN'T TAG. RUN TUBING BACK INTO 1200', PUMPED ANOTHER 35 SX'S CEMENT, PULLED TUBING OUT AND SHUT DOWN FOR DAY. CAME BACK ON 2-17-16, TAGGED CEMENT AT 460'. PUMPED CEMENT FROM 460', CIRCUALTED ON UP OUT OF BOTH CASINGS. PULLED TUBING OUT AND TOPPED OFF SEVERAL TIMES.

Top	Bot	Thru	Comments
3315	3330	CSG	

Remarks: DENIED TA - FAILED MIT FOR TA. PERF TECH #13153. QUALITY OILWELL CEMENT #1319 ON 2-16-16 AND #1320 ON 2-17-16.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

no
2-26-16

JK