

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21122-00-01
Spot: SENWNWSE Sec/Twnshp/Rge: 24-31S-22W
2014 feet from S Section Line, 2012 feet from E Section Line
Lease Name: LORI Well #: 24-10
County: CLARK Total Vertical Depth: 6300 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6130		WITH 2 SX CMT
PROD	5.5	6299	2557	WITH 250 SX CMT
SURF	8.625	643		WITH 225 SX CMT

Well Type: EOR UIC Docket No: E27125.1 Date/Time to Plug: 02/11/2016 11:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: JEFF WERTH Company: H-D OILFIELD SERVICE, INC. Phone: (785) 798-7677

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2016 3:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 6130' WITH 2 SX CMT. 1ST PLUG AT 1020' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 680' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6180	6290		

Received
KANSAS CORPORATION COMMISSION
FEB 19 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Larry J. Adams ECRS
(TECHNICIAN)

RECEIVED
FEB 16 2016
KCC DODGE CITY

Form CP-2/3

NO
2-26-16
cc-MIC
KMS