

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21112-00-02
Spot: W2SESE Sec/Twnshp/Rge: 24-31S-22W
668 feet from S Section Line, 1029 feet from E Section Line
Lease Name: KELLY OWWO Well #: 24-16
County: CLARK Total Vertical Depth: 6900 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4340		WITH 2 SX CMT
CIBP		5990		
PROD	5.5	6290	1098	WITH 325 SX CMT
SURF	8.625	642		WITH 325 SX CMT

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 02/16/2016 11:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: JEFF WERTH Company: H-D OILFIELD SERVICE, INC. Phone: (785) 798-7677

Proposed
Plugging
Method:

CIBP @ 4340' WITH 2 SX CMT. PLUG AT 1020' WITH 12 SX GEL & 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 02/16/2016 3:30 PM

Witness Type: COMPLETE (100%)
KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4340' WITH 2 SX CMT. CUT CASING AT 2269'. COULD NOT PULL CUT CASING AT 2451'. COULD NOT PULL. CUT CASING AT 2232'. WELL KICKED OFF BLOWING GAS & OIL. PUMPED 75 SX CMT/DISPLACED TO 1500' TO PLUG CASING CUT & KILL WELL. CUT CASING AT 1098'. 1ST PLUG AT 1024' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 680' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT TO SURFACE. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4396	4598		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
FEB 17 2016
KCC DODGE CITY

Signed Tony Adams EC25
(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

no
2.26-16 Form CP-2/3