

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Reno County, Sec. 27 Twp. 23s Rge. 4 (E) W (W)
Location as "NE/CNWKSWK" or footage from lines SW NE NE
Lease Owner S & K Oil Company
Lease Name Penner Well No. 2
Office Address P.O. Box 559 Tulsa, Oklahoma 74101
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed 9-II 19 73
Application for plugging approved 9-13 19 73
Plugging commenced 10-24 19 73
Plugging completed 6-22 19 74
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 3325' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,459'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3325' to 3290'. Dumped 5 sx of cement. Squeezed well with 4 sx of hulls; 25 Gel; 2 Hulls; 150 sx of cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1974

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 1974.

My commission expires December 31, 1977

[Signature]
Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: S & K Oil Company DRILLING COMMENCED: 1/31/69
Box 682
Tulsa, Oklahoma

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: 2/6/69
505 Union Center
Wichita, Kansas

CASING RECORD: 10 3/4" surface casing LOCATION: Penner # 2
set at 257', 260 sacks SW NE NE Sec. 27,
cement. 23S-4W, Reno
5 1/2" pipe set at County, Kansas
3,302', 150 sacks cement.


2-12-89
RECEIVED
FEB 12 1969
S & K OIL CO.
LOUISIANA, ET AL

0	-	18	Soil
18	-	86	Sand
86	-	294	Sandy shale
294	-	655	Lime
655	-	810	Lime and shale
810	-	850	Lime
850	-	1280	Lime with shale streaks
1280	-	1994	Shale and shells
1994	-	2913	Lime
2913	-	3278	Shale and shells
3278	-	3325	Lime
3325	-		TOTAL DEPTH

I hereby certify the foregoing statements to be true and correct,
to the best of my knowledge.

GRAVES DRILLING CO., INC.

By J. Graves
President



STATE OF KANSAS)
) ss
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this
th day of February, 1969.

My commission expires: July 28, 1970

Copied & filed
2-12-69

Mary Ann Scott
Mary Ann Scott, Notary Public