

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 27 Twp. 23S Rge. 4W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW

Lease Owner Hinkle Oil Company

Lease Name Banz Well No. 1

Office Address 1016 Union Center Bldg. - Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed October 6, 1966

Application for plugging filed October 6, 1966

Application for plugging approved October 6, 1966


Plugging commenced October 6, 1966

Plugging completed October 6, 1966

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3675 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	211'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 300' w/mud.  
Put plug w/1 sx hulls.  
Mixed 25 sx cement. Top  
plug @40' w/1 sx hulls &  
10 sx cement to bottom of  
cellar.

10-24-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company

Address 1720 Wichita Plaza - Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
George A. Angle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle

1720 Wichita Plaza - Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of October, 19 66

Jean Dellar  
Notary Public.

My commission expires 5-22-70

15-155-30148-0000

DRILLERS LOG

Banz No. 1

CASING RECORD:  
13" @ 211'  
w/125 sx cement

COMPANY: Hinkle Oil Company  
CONTRACTOR: Red Tiger Drilling Co.  
COMMENCED: Sept. 24, 1966  
COMPLETED: Oct. 6, 1966

DESCRIPTION:  
NW SE NW  
27-23S-4W  
Reno Co., Ks.

ELEVATION:

TOTAL DEPTH: 3675'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	140	
Shale	140	213	
Shale & Shells	213	400	
Salt	400	716	
Lime & Shale	716	873	
Lime	873	966	
Shale & Lime	966	1063	
Shale & Shells	1063	1660	
Shale & Lime	1660	2870	
Lime	2870	3350	
Cherty Lime	3350	3458	
Lime & Shale Cherty	3458	3492	
Cherty Lime	3492	3537	
Lime & Shale	3537	3675	

OIL & GAS  
 STATE COMMISSION  
 OCT 24 1966  
 COMPLETION DIVISION  
 WICHITA, KANSAS  
 10-24-66

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle  
George A. Angle

Subscribed and sworn to before me this 12th day of October, 1966.

Jean Shellen  
Notary Public

My Commission Expires:

5-22-70