

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-155-20064-0000

API NUMBER None

LEASE NAME Banz

WELL NUMBER 3

4950 Ft. from S Section Line

3650 Ft. from E Section Line

SEC. 27 TWP. 23S RGE. 4 W or (W)

COUNTY Reno

Date Well Completed 6/22/68

Plugging Commenced 8/28/00

Plugging Completed 8/29/00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR TGT Petroleum Corp.

ADDRESS 7570 W 21st-Bldg. 1010-D, Wichita, Ks.

PHONE# (316) 773-2266 OPERATORS LICENSE NO. 5118

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Miss-Osage Depth to Top 3340 Bottom 3345 T.D. 3430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	231'	-0-
				8 5/8	653	-0-
				4 1/2	3426	2292.4'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Set bridge plug @ 3375', dump four sacks on top of plug. Pumped 50 sacks at 692'. Pulled pipe to 250' and circulated 75 sacks to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mike Kelso License No. 31528

Address PO Box 467, Chase, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

RECEIVED  
KANSAS CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Sedgwick, ss.

JAN 08 2001

B. Lynn Herrington (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have known the contents, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

(Address) 7570 W 21st-Bldg. 1010-D  
Wichita, Ks. 67205



Subscribed and sworn to before me this 29th day of December, 2000

Judith K. Moser  
Judith K. Moser Notary Public


My Commission Expires: May 17, 2001

ROTARY DRILLERS' LOG

OPERATOR: Rosen Oil Company DRILLING COMMENCED: June 17, 1968  
 605 Sutton Place  
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: June 22, 1968  
 505 Union Center  
 Wichita, Kansas 67202

CASING RECORD: 9 Jts. 231' 10-3/4" LOCATION: Banz No. 3  
 cemented with 275 sacks NW NE NW  
 22 Jts. 653' 8-5/8" Section 27-23S-4W  
 cemented with 100 sacks Reno County, Kansas  
 107 Jts. 3426' 4-1/2"  
 cemented with 100 sacks



0 - 235	Sand & shale
235 - 640	Lime & shale
640 - 653	Shale & lime
653 - 1185	Lime & shale
1185 - 2385	Shale & lime
2385 - 2580	Shale, lime & sandy shale
2580 - 2908	Lime
2908 - 3050	Lime & shale
3050 - 3170	Shale & lime
3170 - 3328	Lime & shale
3328 - 3430	Lime
3430	Rotary Total Depth

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 JAN 08 2001  
 CONSERVATION DIVISION  
 WICHITA, KS

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.  
 By Phil Graves  
 President

STATE OF KANSAS )  
 ) ss:  
 SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 25th of June, 1968.

Betty Brandt  
 Betty Brandt Notary Public

My commission expires: May 9, 1971