


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kingman County. Sec. 13 Twp. 27S Rge. (X) 5 (W)
Location as "NE/CNW/SW" or footage from lines C SW SE SW
Lease Owner Gulf Oil Corporation
Lease Name Ast Well No. 1
Office Address 316 Union Center Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-26 19 59
Application for plugging filed 8-27 19 59
Application for plugging approved (Verbally 8-27-59) 8-31 19 59
Plugging commenced 8-27 19 59
Plugging completed 8-27 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -- 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well F. W. Hampel
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4278 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	284'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from -- feet to -- feet for each plug set.

Mudded hole from 4278' to 240'. Placed HOWCO plug and 1/4 sack hulls at 240'.
Cemented through drill pipe from 240' to 135' with 35 sacks cement. Mudded hole to 40'. Placed HOWCO plug and 1/4 sack hulls at 40'. Capped to top of surface casing with 15 sacks cement.

RECEIVED
STATE CORP. COM. FILED
SEP 14 1959
WICHITA, KANSAS

Attached is Driller's Formation Log on this well. The log was not available at the time the Plugging Application was filed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Company
Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas A. Trax (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
316 Union Center Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 59

My commission expires 2-4-63

Ray W. Rowen
Notary Public.

PLUGGING
FILE SEC. 13 Twp. 27 R. SW
BOOK PAGE 63 LINE 33

AST WELL NO. 1

SW SE SW Section 13-27S-5W
 Kingman County, Kansas
 Gulf Oil Corporation

8-5/8" O. D. casing cemented at 283'

Drilling commenced 8-8-59
 Drilling completed 8-27-59

FROM	TO	FORMATION	REMARKS
0'	30'	Surface clay	
30	50	Red bed	
50	70	Sand	
70	240	Shale & shells	
240	285	Shale	8-5/8" O. D. casing cemented with 250 sacks at 283'
285	1005	Shale & shells	
1005	1230	Shale & lime	
1230	1350	Lime & shale	
1350	1490	Shale & lime	
1490	1670	Lime & shale	
1670	1860	Shale & lime	
1860	2005	Lime & shale	
2005	2365	Shale	
2365	2455	Lime & shale	
2455	2575	Shale & lime	
2575	3391	Lime	
3391	3548	Lime & shale	
3548	3845	Lime	
3845	4025	Lime & shale	
4025	4095	Shale	
4095	4150	Shale & sand	
4150	4160	Lime	
4160	4245	Sand	
4245	4278	Sand & lime	

T. D. 4278'

RECEIVED
 STATE CORPORATE TAX COMMISSION
 SEP 14 1959
 CONSERVATION DIVISION
 Dry hole - well plugged

PLUGGING
 FILE SEC 13 T 27 R 5W
 BOOK PAGE 63 LINE 33