

15-155-30148-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TGT Petroleum Corp.ADDRESS 209 E. William - Wichita, Ks.PHONE # (316) 262-6489 OPERATORS LICENSE NO. 5118Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YesWhich KCC/KDHE Joint Office did you notify? Dist. #2Is ACO-1 filed? No If not, is well log attached? YesProducing formation Mississippi Depth to top 3303 bottom 3349 T.D. 3685

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| Surface | | 0 | 212 | 13" | 212' | None |
| | | 0 | 714 | 8 5/8" | 714 | None |
| | | 0 | 3670 | 5 1/2" | 3670 | None |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plug back from 3684' to 3035' with pea gravel and 25 sacks cement. Fill 5 1/2" from 300' to surface with 60 sacks cement. Fill back-side of 5 1/2" with 50 sacks cement. Fill backside of 8 5/8" with 50 sacks. All were filled to top of ground.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Service License No. 5823
Address Burrton, Ks.

STATE OF Kansas COUNTY OF Sedgwick, ss.


B. Lynn Herrington (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

APR 21 1986

(employee of operator) or

(Signature)

B. Lynn Herrington
209 W. William - Wichita, Ks.SUBSCRIBED AND SWORN TO before me this 18 day of April, 1986
Wichita, KansasMy Commission expires: May 17, 1989API NUMBER Comp. date 4-29-67LEASE NAME BanzWELL NUMBER 1SPOT LOCATION NW SE NWSEC. 27 TWP. 23S RGE. 4 ~~XX~~^(W)COUNTY RenoDate Well Completed 4-29-67Plugging Commenced 4-4-86Plugging Completed 4-10-86

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

BANZ #1 (OKNO)
 NW SE NW SECTION 27-23S-4W
 RENO COUNTY, KANSAS

OLD INFORMATION: WAS HINKLE OIL CO. #1 BANZ
 SPUD 9-26-66, SET 8-5/8" CASING @ 714' w/150 SACKS CEMENT AND 13"
 CASING @ 212' w/225 SACKS CEMENT. D & A @ 10-5-66. TD 3675'.


NEW INFORMATION:

COMMENCED: APRIL 26, 1967
 COMPLETED: APRIL 29, 1967

OPERATOR - Rosen Oil Co., Inc.

| DEPTH | FORMATION | REMARKS |
|-------|-----------|--|
| FROM | To | |
| C | 40 | CEMENT |
| 40 | 3675 | MUD AND CEMENT |
| 3675 | 3685 | LIME |
| 3685 | TD | RAN 117 JOINTS 5 $\frac{1}{2}$ " CASING SET @ 3670' w/150 SACKS CEMENT. |

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL WASHED DOWN AND DEEPENED IN THE NW SE NW SECTION 27-23S-4W, RENO COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.



E. E. HALL

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)
)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 2ND DAY OF MAY, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

STATE CORPORATION COMMISSION
 APR 21 1966

CONSERVATION DIVISION
 Wichita, Kansas


 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.