

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

TREGO County. Sec. 3 Twp. 11 Rge. 21 (E) (W) EST

Location as "NE/CNW/SW" or footage from lines SE NW NW

Lease Owner THEODORE GORE

Lease Name ELLA LEWIS Well No. 3

Office Address 400 BROWN BLDG., WICHITA 2, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed FEBRUARY 20 1957

Application for plugging filed FEBRUARY 20 (VERBAL) 1957

Application for plugging approved _____ 19____


Plugging commenced FEBRUARY 20 1957

Plugging completed FEBRUARY 20 1957

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well ELDON PETTY

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3780 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	154'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

BOTTOM PLUG SET AT 150' WITH 1/2 SACKS HULLS, 15 SACKS CEMENT.

TOP PLUG SET AT 40' WITH 1/2 SACKS HULLS, 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY

Address 400 BROWN BLDG., WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK

I, DAN J. KORNFELD ~~CONTRACTOR FOR~~ CONTRACTOR FOR ss.

(operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

DAN J. KORNFELD
400 BROWN BLDG., WICHITA 2, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 25TH day of FEBRUARY, 19 57

[Signature]
CHARLOTTE STANLEY,
Notary Public.

My commission expires JUNE 7, 1960.

PLUGGING
FIL' 'EC 3 T. 11 R. 21W
BOOK PAGE 143 LINE 20

02-27-57

LOG

COMPANY: THEODORE GORE, WICHITA, KANSAS

CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

FARM: ELLA LEWIS No. 3

LOCATION: SE NW NW OF SEC. 3-11-21, TREGO COUNTY, KANSAS

COMMENCED: FEBRUARY 11, 1957

COMPLETED: FEBRUARY 20, 1957

ELEVATION: 2127 K.B.

0	TO	163	CLAY, SHALE AND SHELLS	TOPS:	
163	TO	1583	SHALE AND SHELLS		
1583	TO	1630	ANHYDRITE	HEEBNER	3371'
1630	TO	2280	SHALE AND SHELLS	TORONTO	3391'
2280	TO	2440	SHALE AND LIME	LANSING K.C.	3412'
2440	TO	2905	LIME AND SHALE	BASE K.C.	3654'
2905	TO	3027	SHALE AND SHELLS	DETRITAL ARBUCKLE	3733'
3027	TO	3130	LIME AND SHALE	ARBUCKLE	3760'
3130	TO	3320	SHALE AND LIME		
3320	TO	3485	LIME AND SHALE		
3485	TO	3695	LIME		
3695	TO	3740	LIME AND SHALE		
3740	TO	3750	LIME		
3750	TO	3780	REWORKED ARBUCKLE		
3780			R.T.D.		

DRY AND ABANDONED

CASING: RAN 154 FT. OF 8 5/8" AND CEMENTED WITH 115 SACKS CEMENT.

CERTIFICATION

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE ELLA LEWIS No. 3, SE NW NW OF SEC. 3-11-21, TREGO COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld

 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 25TH DAY OF FEBRUARY, 1957.

Charlotte Stanley

 CHARLOTTE STANLEY, NOTARY PUBLIC

MY COMMISSION EXPIRES JUNE 7, 1960.

PLUGGING
 SEC 3 T 11 R 21W
 LOCK PAGE 143 LINE 20

RECEIVED
 THE STATE OF KANSAS
 DEPARTMENT OF REVENUE

02-27-57