


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-195-00969-0000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

TREGO County, Sec. 3 Twp. 11 Rge. 21 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner THEODORE GORE
Lease Name ELLA LEWIS Well No. 5
Office Address 400 BROWN BUILDING WICHITA 2, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed MARCH 22, 1957 19
Application for plugging filed MARCH 22, 1957 (VERBAL) 19
Application for plugging approved 19
Plugging commenced MARCH 22, 1957 19
Plugging completed MARCH 22, 1957 19
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation Depth to top Bottom Total Depth of Well 3745' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	166'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

BOTTOM PLUG SET AT 150' WITH 1/2 SACKS HULLS, 15 SACKS OF CEMENT.
TOP PLUG SET AT 40' WITH 1/2 SACK OF HULLS, 10 SACKS OF CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 400 BROWN BUILDING WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, DAN J. KORNFELD, CONTRACTOR FOR (employee of owner) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Dan J. Kornfeld*
DAN J. KORNFELD
400 BROWN BUILDING, WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 2ND day of APRIL, 19 57

Hazel Pierson
HAZEL PIERSON
Notary Public.

My commission expires JULY 2, 1958

PLUGGING
FILE SEC. 3 T. 11 R. 21W
BOOK PAGE 2 LINE 5

04-05-57

LOG

COMPANY: THEODORE GORE, WICHITA, KANSAS

CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

FARM: ELLA LEWIS # 5

LOCATION: NE SE NW SEC 3-11-21 TREGO COUNTY, KANSAS

COMMENCED: MARCH 11, 1957

ELEVATION: 2104 K.B.

COMPLETED: MARCH 22, 1957

POTENTIAL: _____

0	TO	166	CLAY, SAND AND SHALE
166	TO	1559	SHALE AND SHELLS
1559	TO	1608	ANHYDRITE
1608	TO	2445	SHALE AND SHELLS
2445	TO	2925	SHALE AND LIME
2925	TO	3005	LIME SHALE
3005	TO	3100	SHALE AND LIME
3100	TO	3278	LIME AND SHALE
3278	TO	3380	SHALE LIME
3380	TO	3630	LIME
3630	TO	3694	LIME SHALE
3694	TO	3699	LIME
3699	TO	3704	LIME SHALE
3704	TO	3714	LIME
3714	TO	3745	ARBUCKLE
		3745	R.T.O.--D AND A

RAN 166' OF 8 5/8 AND CEMENTED WITH 115 SACKS CEMENT.
SET

TOPS:	ANHYDRITE	1559'
	TOPEKA	3128'
	HEEBNER	3337'
	TORONTO	3357'
	LANSING-KANSAS CITY	3374'
	BASE OF KANSAS CITY	3608'
	REWORKED ARBUCKLE	3685'

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE ELLA LEWIS NO. 5 NE SE NW OF SEC. 3-11-21, TREGO COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 2nd DAY OF April 1957

Hazel Pierson
HAZEL PIERSON, NOTARY PUBLIC

MY COMMISSION EXPIRES JULY 31 1958

PLUGGING
FILE SEC. 3 T. 11 R. 21W
BOOK PAGE 2 LINE 5

VED
COMMISSION
APR 5 - 1957
04-05-57
DIVISION
WICHITA, KANSAS