

**Give All Information Completely**  
**Make Required Affidavit**  
**Mail or Deliver Report to:**  
**Conservation Division**  
**State Corporation Commission**  
**211 No. Broadway**  
**Wichita, Kansas**

15-167-04198-0000

A 4x4 grid with a central '4' and a circled 'X' in the top-right quadrant.

Russell County, Sec. 34 Twp. 15 Rge. 15 (E) X (W)  
 Location as "NE/CNW/SWK" or footage from lines NE NE NW  
 Lease Owner: Kim Oil Company, Incorporated  
 Lease Name Michaelis Well No. 1  
 Office Address Russell, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed January 11 1962  
 Application for plugging filed January 11 1962  
 Application for plugging approved January 11 1962  
 Plugging commenced January 11 1962  
 Plugging completed January 11 1962  
 Reason for abandonment of well or producing formation' Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3440 Feet  
Show depth and thickness of all water, oil and gas formations.

### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0	225'	8 5/8"	225'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 210'. Plug and one-half sack hulls @ 210' and 25 sacks cement, mud up to 35', plug and one-half sack hulls and 10 sacks of cement.

STATE 10 1562 01-18-62  
JAN 10 1962  
CONSERVATION DIVISION  
MICHIGAN DEPT. OF NATURAL RESOURCES

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Terrel Drilling & Producing

Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, SS. Joe K. Branum, Contractor (~~Manager of Works, at order of sponsor~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

So help me God.  
*Joe E. Brannan*  
 754 East Wichita, Russell, Kansas  
 (Address)

SUBSCRIBED AND SWORN to before me this 11th day of January, 1962

My commission expires November 13, 1963

**Notary Public.**

# WELL LOG

OPERATOR: Kim Oil Company, Incorporated  
Russell, Kansas  
LEASE: Michaelis  
NW/4 of 34-153-15W  
Russell County, Kansas

CONTRACTOR: Terrel Drilling & Producing  
Russell, Kansas  
COMMENCED: January 1, 1962  
COMPLETED: January 11, 1962  
LOCATION: NE-NE-NW

WELL: No. 1

## DEPTHS & FORMATIONS

Surface Clay	30'	Lime & Shale	2050'
Post Rock	40'	Lime	2320'
Shale & Shells	210'	Lime	2460'
Shale & Sand	964'	Shale & Shells	2735'
Anhydrite	1000'	Lime & Shale	3060'
Shale	1250'	Lime	3155'
Shale & Shells	1625'	Lime & Shale	3306'
Shale & Lime	1865'	Lime	3390'
		Shale & Lime	3440' R.T.D.

STATE OF KANSAS

COUNTY OF RUSSELL SS

JAN 12 1962  
NOTARY PUBLIC  
KANSAS

Joe K. Braman, owner of Terrel Drilling & Producing, being first duly sworn on oath says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Joe K. Braman  
Joe K. Braman

Subscribed and sworn before me this 12th day of January, 1962.

Mary Anna Braman  
Notary Public

Russell County

My Commission Expires November 13, 1963.