

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name W.L. Kirkman, Inc.

Complete Address Box 18611-Wichita, Kansas. 67207

Lease Name Kachelman Well No. 1

Location C NW NE SW Sec. 21 Twp 24s Rge. 13 (E) (W) X

County Stafford Total Depth 2010

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176-Chase, Kansas. 67524 License No. 683

Operation Completed: Hour 10:30 Am. Day 10 Month 4 Year 1979

The above well was plugged as follows:

434'-8 5/8" casing w/385 sax cement. 4 1/2" casing set at 1993' w/125
sax cement. Plug back to 1963'. Top pref., at 1888'-Allied mixed &
pumped 35 sax common cement in 4 1/2" casing. Top at 1875'-Pull 1515'
4 1/2" casing. Allied mixed & pumped 5 sax hulls-20 sax gel-Release
plug-Mixed & pumped 135 sax 50/50 posmix cement w/2% gel & 3% cc to
top of casing. Shut in w/ 100# pressure.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1979 4-12-79

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

VOICED

u. 4-13-79
INV. NO. 9428.0