

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name W.L. Kirkman, Inc.

Complete Address Box 982, Pratt, Ks. 67124

Lease Name Owen Well No. 1

Location C E/2 W/2 NE Sec. 21 Twp. 24s Rge. 13 (E) (W) X

County Stafford Total Depth 2005

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:15 Am. Day 11 Month 12 Year 1979

The above well was plugged as follows:

409' 8 5/8" casing w/285 sax cement. 4 1/2" casing set at 1998' w/125  
sax cement. Sun mixed & pumped 30 sax common cement in 4 1/2" casing  
to 1850'-Pull 1585' 4 1/2" casing-Sun mixed & pumped 8 sax hulls-25  
sax gel-125 sax 50/50 posmix cement w/4% gel & 3% cc, to top of casing.  
Shut in w/200# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 13 1979 12-13-79

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 12-14-79

INV. NO. 1089-w