

15-185-00469-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten initials*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
*2-2-70*

Operator's Full Name Braden-Deem Inc.  
*for*

Complete Address Petroleum Inc.

Lease Name 300 W Douglas Wichita, Ks 67202

Well No. Beckerdite 1

Location SE/SW/NW Sec. 21 Twp. 24 Rge. 13 (E) (W) X

County Stafford Total Depth 3 876

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 9:30 AM Day 31 Month 1 Year 1970

The above well was plugged as follows:  
237 ft. of 8 5/8 surface pipe cemented with 200 sacks cement. Did  
circulate. 3875 ft of 4 1/2 long string cemented with 100 sacks cement.  
Top Perforated, 3622, sanded back to 3600 with 3 sacks cement with  
bailer. 2323 4 1/2 pulled. Mud to 200 ft, 10 ft rock bridge, 25 sacks  
cement. Mud to 40 ft. ~~10 sacks cement to surface.~~ 10 ft rock bridge.  
10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. Russell Belarstain*  
Well Plugging Supervisor

DATE 2/2/70  
INV. NO. 1348-W