

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
300 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
12-16-63
DEC 16 1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Webb Hill of Mack Oil Co. has this

date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name: Phil Well No. # 1

Location: C NE SE Sec. 13 Twp. 27 Rge. 6 (E) (W) W

County Kingman Total Depth 4185 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

287' of 8 5/8" surface pipe, cemented with 225 sacks.
Fill hole with drilling mud to 275', 1st cementing plug,
bridge with hulls, cement with 35 sacks. Fill hole with
drilling mud to 40', 2nd cementing plug, bridge with hulls,
cement with 10 sacks to base cellar. Bridge and cement rat
& mouse hole with 5 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent