

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 CONSERVATION DIVISION
 WICHITA, KANSAS

APR 24 1967

4-26-67

CONSERVATION DIVISION
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill,
 filed April 12, 1967.

Dear Sir:

Mr. Percy Hall of Pickrell Drilling Company has this
 date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Ks.

Lease Name: French Well No. # 1

Location: C NW NW Sec. 9 Twp. 27 Rge. 6 (E)(W) W

County Kingman Total Depth 4075' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

203' of 8 5/8" surface pipe, cement circulated with 165 sacks. Fill
hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent