



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

October 26, 1972

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1972
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Jack Fox of N K O Drilling Co. has this
date requested permission to plug the following described well:

Mr. Fox guarantees payment of the plugging fee.

Operator's full Name: Trans American Oil Company

Complete Address: 21 W. Second--Suite 23, Hutchinson, Kansas 67501

Lease Name: Wiegel Well No. 1

Location: SE NE SE Sec. 9 Twp. 23 Rge. 7 (E) (W) X

County: Reno Total Depth 3654' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fox was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and 1/4 sack hulls to 240' and
cement hole with 25 sacks cement through drill pipe. Fill hole with mud
to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent