

State of Kansas



15-155-20121-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 22, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Drlg. Co., Inc. has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Comet Petroleum Corporation

Complete Address: 608 Union Center, Wichita, Kansas 67202

Lease Name: Griffin Well No. 1

Location: C SW SW Sec. 17 Twp. 23 Rge. 7 ~~(S)~~ (W) X

County Reno Total Depth 4005' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

Fill hole with mud to 210'. Push plug and 1/4 sack hulls to 210' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent