


15-185-10464-0000

Form CP-3  
Rev. 6-26-62

 KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1966

CONSERVATION DIVISION  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Johnston Well No. # 1

Location NE SE SE Sec. 29 Twp. 24 Rge. 13 (E) (W)W

County Stafford Total Depth 3895'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bned, Kansas License No. 574

Operation Completed: Hour 6:30 PM Day 10th Month Feb. Year 1966

The Above well was plugged as follows:

403' of 8 5/8" surface pipe, cemented with 350 sacks. 3894' of 5 1/2" long  
string, cemented with 100 sacks. Top perferation 3775'. Bottom plug was  
pushed to 3775', and 50' of sand, and cemented with 5 sacks, through the  
dump bailer. 2610' of 5 1/2" long string was recovered from the hole. Fluid  
was up in the hole. Bridge plug was pushed in fluid to 270', rock bridge  
from 270' to 260'. 5 sacks of cement and 8% calcium chloride was mixed in  
a barrel, and put on plug at 260', through the dump bailer, and let set for  
3 hours. Fluid in the hole was bailed dry, and 20 sacks of cement was added  
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and  
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

Date 2/15/66

INV. NO. 2429-W