

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
241 North Water
Wichita, KS 67202

API Number 15 - - 60 (of this well)

Operator's Full Name Stepco Oil Co.

Complete Address Box 227, Ellinwood, Ks. 67526

Lease Name Toland "B" Well No. 1

Location S/2 SW NE Sec. 31-Twp. 24s Rge. 13 (E) (W)X

County Stafford Total Depth 4300

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12 N. Day 23 Month 7 Year 1980

The above well was plugged as follows:

258' 8 5/8" casing W/225 sax cement. 4 1/2" casing set at 4125' W/300
sax cement. Plug back to 4100'-Top pref's at 3688-92'-Push plug to
3700'-Sand back to 3650'-Top sand w/4 sax mixed cement W/dump bailer.
Pull 2830' casing-Allied mixed & pumped 8 sax hulls-25 sax gel-100
sax common cement w/4% gel & 4% cc in 8 5/8" casing to top of casing.
Shut in W/150# pressure.

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 7-25-80
INV. NO. 2698-W