

15-185-01130-0000

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Rex & Morris Drilling Co. - Petroleum Inc.Complete Address: P. O. Box 334, Eldorado, KansasLease Name Harter Well No. # 1Location NW SW NW Sec. 31 Twp. 24 Rge. 13 (E) (W) WCounty Stafford Total Depth 4138Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Ralph Comstock Pipe Pulling Co.Address: Stafford, Kansas License No. 490Operation Completed: Hour 9:30AM Day 31st Month May Year 1963

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cement circulated with 250 sacks.4138' of 4 1/2" long string, cemented with 150 sacks. Perferated 4044'to 60'. Sanded to 4030', cemented with 3 sacks. Fluid level was up inhole. 6 sacks cement was mixed and set on plug at 225', with 10' rockbridge, through dump bailer and let set over night, fluid in holebailed down, and 14 sacks cement was added to plug. Hole was filledwith mud to 40'. 10' rock bridge, cemented with 10 sacks to base cellar.2063' of 4 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/4/63INV. NO. 7191-WSigned: Archie Elving

Well Plugging Supervisor