

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- - not available

SE 1/4, Sec. 31, T 24 S, R 13 W/E  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Bowker "G" Well # 1

Operator: Petroleum, Inc.  
Name & Box 1447  
Address Great Bend, KS 67530

County Stafford

Well Total Depth 4266 feet 138.64  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhole Eng. License Number 6111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:30 am Day: 24 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2 set at 4264' PBTB 3990. Top perf 3804. Sand back to 3750. Pump 5 sx cement with bailer. Recovered 3000' of 5 1/2. Squeezed well with 3 sx hulls, 20 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls and released 8 5/8" plug followed with 100 sx cement.

Signed J. A. Mill  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00 pm Day: 24 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4264 PBTB 3990. Top perf 3804. Sand back to 3750. Pump 5 sx cement with bailer. Recovered 3000' of 5 1/2. Squeezed well with 3 sx hulls, 20 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls and released plug followed with 100 sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3% cc. by Allied

RECEIVED  
STATE CORPORATION COMMISSION  
2-2-84  
FEB 02 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed J. A. Mill  
(TECHNICIAN)

INVOICED

DATE 2-6-84

INV. NO. 0074

1-24