

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION 20W-21E-21ESEC. 27 TWP. 24 RGE. 13-10Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease McNaghten - "A"Operator The Atlantic Refining Co. Address Box #17 - G. Band - KansasField _____ County StaffordTotal Depth 4110 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 12 1/2 - 247 ft. Circulated with cement
7" casing set at 4097 ft. - 200 sacks of cement.
Plugged back to 3660 ft with Lane Wells Plug &
cement - Filled with shot from 3660 ft to 3630 ft
Dumped 5 sacks of cement at 3630 ft - Shut off
& Pulled the 7" casing - mud to 247 ft. Set
Rock Bridge & 40 sacks of cement at 247 ft
Mud to 36 ft - Bridge & 10 sacks of cement
at the surface

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 X 1951

8-3-51

CONSERVATION DIVISION

District Conservation Agent

Date

8-1-51