

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Well Plugging Authority,
issued March 6, 1968.

Operator's Full Name Murfin Drilling Company

Complete Address: 617 Union Center Bldg., Wichita, Kansas 67202

Lease Name McNaghten Well No. # 1

Location NE NE NE Sec. 27 Twp. 24 Rge. 13 (E) W

County Stafford Total Depth 4134'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Russ Casing Pulling, Inc.

Address: Box 1082, Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 2:45 PM Day 8th Month March Year 1968

The Above well was plugged as follows:

263' of 8 5/8" surface pipe, cemented with 200 sacks. 4133' of 5 1/2" long string, cemented with 150 sacks. Plug back T.D. 3750'. Top perforation 3634'. Bottom of the hole was sanded to 3600', and cemented with 5 sacks, with cement from 3600' to 3560'. 2750' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 250', bridge plug and rock bridge from 250' to 240'. 4 sacks of cement was mixed in a barrel, and put on plug at 240', through the dump bailer, and let set over-night. Next day hole was bailed dry; and 21 sacks of cement was added to the plug, with cement from 240' to 165'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

D...E 3/11/68
INV. NO. 7398-u