

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 187-10

LOCATION CE6-E<sup>1</sup>/<sub>2</sub>-7E<sup>1</sup>/<sub>4</sub>

SEC. 27 TWP. 24 RGE. 13-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3-A Lease McNaghton

Operator The Atlantic Refining Co Address Box 17 - La Bend - Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 4100 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 450 ft. Circulated with cement  
7" casing set at 409 ft - cemented - Plugged back to 4080 ft  
with Chat - Shot off & pulled the 7" casing - Run up 6 sacks of  
cement at 4080 ft - Filled with mud to 450 ft - Set Rock  
Bridge & 25 sacks of cement at 450 ft - Mud to 30 ft -  
Bridge & 10 sacks of cement at the surface.

Patterson & Son - Plugging Contractors

SEP 9 X 1950

9-9-50

STATE CORPORATION  
COMMISSION

C. D. Strough  
District Conservation Agent

Date 9-7-50

**PLUGGING**  
FILE SEC 27 T 24 R 13W  
BOOK PAGE 127 LINE 10