

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 16 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Harrison "B" Well No. # 1

Location NE SW SW Sec. 17 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 4210

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co. Inc.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 9:00AM Day 14th Month May Year 1963

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cement circulated with 200 sacks. 3990' of
5 1/2" long string, cemented with 150 sacks. Plugged back to 3792'. Perfor-
ation 3658' to 3666', Sanded to 3640', cemented with 5 sacks. Fluid was
moving up in hole and a squeeze job was necessary. 20 sacks of mud was
pumped, ahead of 65 sacks of cement in the hole, through 8 5/8" swage.
Next morning cement had floated down to 80' in hole. Hole was filled
with mud to 35', 10' rock bridge, cemented with 8 sacks to base cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 5/15/63
INV. NO. 7082-W

Signed: Audie Elving
Well Plugging Supervisor