

15-185-12174-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 19 Twp. 24 Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines E/2 SE SW
Lease Owner Raymond Oil Company, Inc.
Lease Name KOELSCH Well No. 1
Office Address 410 Fourth National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 30 19 62
Application for plugging filed April 6, 19 62
Application for plugging approved April 9, 1962 19
Plugging commenced March 30 19 62
Plugging completed March 30 19 62
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. LacKamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4184 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @240' w/1/4 Sx. hulls on top and bottom and 25 Sx. through drill pipe.

Set plug @35' w/1/4 Sx. hulls on top and bottom and 10 Sx. cement.

2 Sx. in Rat Hole.

4-11-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Raymond Oil Company, Inc.
Address 410 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.
Pat Raymond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Pat Raymond
410 Fourth National Bank Building, Wichita
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of April, 19 62

My commission expires December 10, 1962

Bernice Boldt
Notary Public.



RAYMOND OIL COMPANY, INC.
 No. 1 KOELSCH
 E/2 SE SW 19-24-13
 Stafford County, Kansas

ELEVATION:
 1939 DF
 1941 KB

Contractor: Raymond Oil Company, Inc. - Rig #6
 Commenced: March 20, 1962
 Completed: March 30, 1962

Casing Record
8 5/8" @275' w/300 Sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Sand	140
Shale	276
Shale, Shells and Red Bed	819
Anhydrite	843
Shale and Shells	1480
Shale and Lime	1875
Lime	2325
Lime and Shale	3205
Lime	3493
Shale and Lime	3605
Lime	4042
Lime, Chert and Shale	4085
Lime	4147
Lime and Sand	4184 TD

RECEIVED
 STATE GEOLOGICAL SURVEY OF KANSAS
 APR 9 1962
 CONSERVATION DIVISION
 4-9-62

TOPS:

Anhydrite	819
Heebner	3456
Brown Lime	3593
Lansing	3621
Base Kansas City	3892
Conglomerate	3915
Conglomerate Chert	3952
Viola	4032
Simpson Shale	4159
Simpson Sand	4173
Rotary Total Depth	4184

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.

Wm. M. Raymond
 Wm. M. Raymond, President

Subscribed and sworn to before me this 5th day of April, 1962.

Bernice Bolt
 Notary Public

