


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 19 Twp. 24 Rge. 13 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SE NW NE
Lease Owner Hilton Drilling Company, Inc.
Lease Name Toothaker Well No. 1
Office Address 2421 Tenth Street, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 1 19 55
Application for plugging filed November 1 19 55
Application for plugging approved November 1 19 55
Plugging commenced November 1 19 55
Plugging completed November 1 19 55
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner
Producing formation None Depth to top Bottom Total Depth of Well 4216 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 230' with heavy mud.
At 230', placed 1/3 sack of hulls, Halliburton plug, 20 sacks of cement (cemented thru drill pipe)
Filled hole to 35' with heavy mud.
At 35', place 1/3 sack of hulls, Halliburton plug, 10 sacks of cement (cement to bottom of cellar)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address McBride Building, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Henry Peacock*
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of November, 19 55

Carroll Reinhardt Leiker

Notary Public.

My commission expires 1-26-59

PLUGGING
FILE REC-19 T-24 R-13 W
BOOK PAGE 13 LINE 202

11-5-55

DRILLERS LOG

Company: Hilton Drilling Company, Inc.

Contractor: Strata Drilling, Inc.

Location: SE NW NE
Section 19-24s-13w
Stafford County, Kansas

Farm Name: Toothaker #1

Commenced: October 19, 1955

Elevation:

Completed: November 1, 1955

Casing Used: 239' of 8-5/8" surface casing

0- 65	surface soil & sand
235	Snd & Shale
773	Red bed
805	Anhydrite
1340	Shale and Shells
1740	Shale & Lime shells
1875	Shale & Lime
2355	Lime & Shale
2590	Shale
2795	Shale & Lime streaks
3105	Shale & Lime
3420	Lime & Shale
3525	Lime and Sandy shale
3615	Lime & Shale
3687	Shale & Lime
3905	Lime
3959	Lime & Chert
4030	Chert, lime, & Shale
4075	Lime & Shale
4113	Lime & Chert
4165	Chert, lime & Shale
4210	Shale & Cherty lime
4216	Lime
4216	Total Depth

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

STRATA DRILLING, INC.

John P. Harlan

JOHN P. HARLAN

Marlene J. Knopf
Notary Public

My commission expired February 4, 1959

11-5-55
RECORDED
STATE OF KANSAS
NOV 5 1955
STAFFORD COUNTY

PLUGGING
FILE NO. 19-24-R-13w
BOOK PAGE 13 LINE 23