

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-185-20076-0000 Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 15 Twp. 24 Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner Dunne-Gardner Petroleum, Inc.
Lease Name Soden Well No. 1
Office Address 300 Schweiter Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil well
Date well completed 12-18 19 67
Application for plugging filed 12-3 19 68
Application for plugging approved 12-4 19 68
Plugging commenced 12-4 19 68
Plugging completed 12-4 19 68
Reason for abandonment of well or producing formation Oil depleted

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production April 30 1968
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren
Producing formation Lansing-Kansas City Depth to top 3751 Bottom 3753 Total Depth of Well 4108 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	325'	None
				5-1/2"	543'	None
				2-1/2"	3817'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 3600', 10 sacks cement
Plug @ 540', 25 sacks cement
Plug @ 50', 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1968
CONSERVATION DIVISION
Wichita, Kansas

12-9-68

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Don Gardner*

300 Schweiter Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 68

My commission expires December 14, 1969

Notary Public.

DRILLERS LOG

#1 SODEN
 SW NW NW Sec. 15-24S-13W
 Stafford County, Kansas

OPERATOR: Dunne-Gardner Petroleum, Inc.
 300 Schweiter Building
 Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
 300 Schweiter Building
 Wichita, Kansas

COMMENCED: November 24, 1967

COMPLETED: December 4, 1967

CASING RECORD: 8-5/8" @ 325' w/325 sx
 5-1/2" @ 543' w/130 sx
 2-1/2" tubing @ 3817' w/750 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	135	Surface sand
135	325	Red Bed and clay
325	778	Red Bed and shale
778	795	Anhydrite
795	1730	Shale and lime
1730	2135	Lime
2135	2285	Broken lime
2285	3626	Lime and shale
3626	3948	Lime
3948	3951	Chert
3951	3985	Cherty lime
3985	4047	Chert
4047	4085	Cherty lime
4085	4108	Lime
4108		Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 9 1968
 CONSERVATION DIVISION
 Wichita, Kansas

12-9-68

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.

Jack D. Dunne
 Jack D. Dunne

Subscribed and sworn to before me this 15th day of December, 1967.

My commission expires:
 December 14, 1969

Martha Jones

 Notary Public