

15-185-22157-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-22,157

LEASE NAME DeBusk

WELL NUMBER 1-29

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2970 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 29 TWP. 24 RGE. 14 (W)

COUNTY Stafford

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P. O. Box 947, Pratt, Kansas 67124

PHONE# (316) 672-7581 OPERATORS LICENSE NO. 5087

Date Well Completed 4-3-85

Character of Well D&A

Plugging Commenced 4-4-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-4-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4440'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	349	8 5/8"	3-26-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plugged well with 170 sxs 60/40 poz, 2% gel, 3% cc as follows: 1420'-50 sxs; 710'-40 sxs; 400'-40 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; water well-15 sxs Job by Sun Cementing. Plug down at 4:15 p.m. on April 4, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Pratt, ss. APR 25 1985

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas  
MARY L. TJADEN  
My Appt. Exp. 3/22/88


(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 85

Mary L. Tjaden  
Notary Public

My Commission Expires: 3/22/88



**Oilfield Services, Inc.**

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

**DRILLER'S WELL LOG**

DeBusk #1-29  
 C S/2 SW NW Sec. 29-24S-14W  
 Stafford County, Kansas  
 Commenced: 3-26-85  
 Completed: 4-4-85  
 API #15-185-22,157  
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	1396	Sand, Shale	Ran 8 joints (340') new, 24#, 8 5/8" surface casing. Set at 349' with 200 sxs Class A, 2% gel, 3% cc. Job by Dowell. Cement did circulate. Plug down at 11:30 p.m. March 26, 1985.
1396	1840	Sand, Lime, Shale	
1840	3880	Lime, Shale	
3880	3970	Lansing	
3970	4130	Lime, Shale	
4130	4160	Mississippi	
4160	4241	Mississippi, Kinderhook	
4241	4400	Kinderhook, Viola	
4400	4440	Arbuckle	
		T.D.	
			RTD. 4440'
			Plugged well with 170 sxs 60/40 poz, 2% gel, 3% cc as follows: 1420'-50 sxs; 710'-40 sxs; 400'-40 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; water well-15 sxs. Job by Sun Cementing. Plug down at 4:15 p.m. on April 4, 1985. State Plugger was out of the Dodge City Kansas office.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
 ARNIE LITTLE, VICE-PRESIDENT

RECEIVED  
 STATE CORPORATION COMMISSION

APR 25 1985

*Mary L Tjaden*  
 NOTARY PUBLIC CONSERVATION DIVISION  
 Wichita, Kansas



My Commission Expires:

3/22/88