

STATE CORPORATION COMMISSION
200 Colorado Darby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,177-0000 ²²¹¹⁷

LEASE NAME Russell

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-33

660 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 33 TWP. 24S RGE. 13 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 100 N. Main, Suite 1000, Wichita, Kansas 67202

PHONE# (316) 262-3596 OPERATORS LICENSE No. 9408

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Date Well Completed 03-10-85

Plugging Commenced 04-29-96

Plugging Completed 04-30-96

The plugging proposal was approved on 04-29-96 (date)

by Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to top 3966' Bottom 4192' r.c.PBD 4165'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface			8.5/8"	286	0
	Production			4 1/2"	4225	2297

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set
Bottom plug; sanded off to 3900' 4 sks of cement. Allied mixed 300 lbs. of hulls, 10 sks of gel, 50 sks of cement 10 sks of gel 100 lbs. of hulls. 125 sks of cement. Maximum pressure 400 lbs, shut in pressure 100 lbs.

Name of Plugging Contractor D.S.& W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corporation

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph F. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525


RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 1996

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 96

Bonnie L. Connell
Notary Public

CONSERVATION DIVISION
WICHITA, KS
USE ONLY ONE SIDE OF EACH FORM
Commission Expires: 04-08-97



Form CP-4
Revised 03-88