


15-185-11989-0000

STATE OF KANSAS
-STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 29 Twp. 14 Rge. (E) 13(W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Aurora Gasoline Co.
Lease Name Vedder Well No. 1
Office Address 1107 Union Natl. Bldg. - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5/30 19 57
Application for plugging filed 5/31 19 57
Application for plugging approved 5/31 19 57
Plugging commenced 5/30 19 57
Plugging completed 5/30 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Brundridge - Hoisington, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4210' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	412'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set wooden plug @ 270', 1/2 sack hulls, mixed 20 sacks cement through drill pipe. 1/2 sack hulls, 5 sacks cement @ 25'.

Name of Plugging Contractor Chief Drilling Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address 1823 Washington - Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
CHIEF DRILLING CO., INC. (Signature) V. Richard Hoover
Ferrell Building - Gt. Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 57
Carmen Reinhardt Leiker
Carmen Reinhardt Leiker Notary Public.

My commission expires Jan. 26, 1959

PLUGGING
FILE SEC. 29 T. 24 R. 13w
BOOK PAGE 16 LINE 43

JUN 1 1957
6-3-57
CONSERVATION DIVISION
Kansas

WELL LOG

No. 1 Vedder

Aurora Gasoline Co.
1107 Union National Building
Wichita, Kansas

No. 1 Vedder
SE SE NE Sec. 29-24-13W
Stafford County, Kansas

Commenced: 5/17/57
Completed: 5/30/57

DRY AND ABANDONED

Contractor: Chief Drilling Co., Inc.
Rotary: 0 - 4210' T.D.

Casing Record: 412' 8 5/8" used 28# Seamless casing with 350
sacks Pozmix cement and 7 sacks Calcium Chloride;
cement circulated.

Figures indicate Bottoms of Formations

Sand	0	-	165
Shale	165	-	412
Red Bed	412	-	820
Shale & Shells	820	-	1784
Shale & Lime	1784	-	1940
Lime	1940	-	2055
Lime & Shale	2055	-	3585
Lime	3585	-	3975
Conglomerate	3975	-	4000
Chert	4000	-	4128
Shale	4128	-	4190
Dolomite	4190	-	4210 T.D.

State of Kansas)
County of Barton)

I hereby certify that the above is a true and correct copy of
Driller's Log of well drilled in the SE SE NE of Sec. 29-24S-13W,
Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, Pres.

Subscribed to and sworn to before me this 30th day of May,
1957.

Carmen Reinhardt Leiker
Carmen Reinhardt Leiker, Notary Public

My commission expires:
Jan. 26, 1959

JUN 1 1957
6-3-57
CONSERVATION DIVISION
KANSAS

PLUGGING		
NO.	T.	R.
PAGE		

PLUGGING		
FILE	SEC. 29	T. 24 R. 13W
BOOK	PAGE	16 LINE 43