

15-185-10464-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 29 Twp. 24 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE  
Lease Owner SANTA-EE PIPE & SUPPLY, INC.  
Lease Name JOHNSTON Well No. 1  
Office Address BOX 562, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) OIL  
Date well completed JUNE 30 1957  
Application for plugging filed JANUARY 29 1966  
Application for plugging approved JANUARY 31 1966  
Plugging commenced JANUARY 29 1966  
Plugging completed FEBRUARY 11 1966  
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE V. ELVING  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3895 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	403.97'	NONE
				5 1/2"	3894'	3117'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3894' - 3775' - PLUG  
3775' - 3725' - SAND  
3725' - 3685' - 5 SACKS CEMENT  
3685' - 290' - MUD  
290' - 270' - ROCK BRIDGE  
270' - 264' - 2 SACKS CEMENT  
264' - 195' - 23 SACKS CEMENT  
195' - 35' - MUD  
35' - 30' - ROCK BRIDGE  
30' - BASE - 10 SACKS CEMENT

4-11-66

APR 17 1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SANTA-EE PIPE & SUPPLY, INC.  
Address P. O. BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
T. L. NUTT

(Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt

P. O. BOX 562, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of MARCH, 1966

My commission expires JULY 31, 1966

Mary M. Swanson  
Notary Public.

15-185-10464-0000

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- AURORA GASOLINE CO. No. 1  
Farm- Johnston

SEC. 29 T. 24 R. 13W  
NE SE SE

Total Depth. 3895'  
Comm. 6-18-57 Comp. 6-30-57  
Shot or Treated.  
Contractor. Chief Drlg. Co., Inc.  
Issued. 9-28-57

County Stafford  
KANSAS



Elevation. 1939' RB

Production. 66 BOPD / 16% wtr.

CASING:

8 5/8" 403.97' w/350 sx cem.  
5 1/2" 3894' w/100 sx cem.

Figures indicate Bottom of Formations.

sand	60
sdv clay-shells	400
shale-red bed	585
sand	610
red bed-shale	818
Anhydrite	840
shale-shells	1700
lime	2235
lime-shale	2420
shale-shells	2890
lime-shale	3545
lime	3895
Total Depth	

TOPS: Scout	
Anhydrite	818
Heebner	3436
Douglas	3474
Brown lime	3573
Lansing	3599
B/Kansas City	3873