

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD

County, Sec. 31 Twp. 24S Rge. (E) 13 (W)

Location as "NE/CNW&SW¼" or footage from lines NW SW NW

Lease Owner REX & MORRIS DRILLING CO., AND PETROLEUM, INC.

Lease Name HARTER Well No. 1

Office Address P. O. BOX 334, EL DORADO, KANSAS 67042

Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL

Date well completed 19 NOVEMBER 19 61

Application for plugging filed 14 MAY 19 63

Application for plugging approved 15 MAY 19 63

Plugging commenced 22 MAY 19 63

Plugging completed 31 MAY 19 63

Reason for abandonment of well or producing formation OIL DEPLETED

If a producing well is abandoned, date of last production 6 MARCH 19 63

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING

Producing formation MISSISSIPPI CHERT Depth to top 4044 Bottom 4060 Total Depth of Well 4138 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE HOLE	WATER	SURFACE	250'RB	8 5/8"OD	245.62'	LEFT IN
MISSISSIPPI CHERT	OIL-GAS-WATER	4044'	4060'	4 1/2" OD	4138'	2036'
(SEE ATTACHED LOG)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH SAND TO 4030', DUMPED 3 SACKS CEMENT, FILLED HOLE WITH DRILLING MUD TO 225', SET PLUG & 10' ROCK BRIDGE AND DUMPED 6 SACKS CEMENT, BAILED HOLE DRY & DUMPED IN 14 SACKS CEMENT, FILLED HOLE WITH DRILLING MUD TO 40', SET 10' ROCK BRIDGE AND DUMPED 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1963 8-27-1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RALPH COMSTOCK PIPE PULLING, INC.

Address 411 SOUTH BUCKEYE, STAFFORD, KANSAS

STATE OF KANSAS, COUNTY OF BUTLER, ss.
A. H. FISHER

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. H. Fisher*

P. O. BOX 334, EL DORADO, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 26TH day of AUGUST, 19 63

My commission expires 8 AUGUST 1966

ELIZABETH DESCHNER

Notary Public.



15-185-01130-0000

Elevation 1952 R.B.
1949 D.F.

HARTER #1

Rex & Morris Drilling Company
and
Petroleum, Inc.

Total Depth: 4138'
Contractor: Rex & Morris Drilling Co.
Commenced: 10-9-61
Completed: 11-19-61
Initial Prod.: 3 MMCFG, 20 BO

Location: NW SW NW
Section 31-24S-13W
Stafford County, Kansas

Casing Record:
8 5/8" @ 250' w/225 sacks
4 1/2" @ 4138' w/100 sacks

FORMATION	DEPTH
Surface Hole	250
Shale	850
Anhydrite	875
Shale and Lime	1775
Lime and Shale	2675
Shale and Lime	2960
Lime and Shale	3485
Shale	3643
Lime	3953
Lime and Shale	4100
Lime	4138

R.T.D. 4138

R.U.S.T., C.O. 4109' Ran Lane Wells GR-N, 4109'
Perf. 4040-60', 14' with 4 shots per foot. Acid 250 gal.
Gas decreased 1/2.
Acid Petrofraced with 7% acid and 9000# sand.
Open flow 7 hrs. Est. 3 MMCFG and 20 BOPD. S.I.

RECEIVED
STATE CORPORATION COMMISSION

406-27 1962

CONSERVATION DIVISION
Wichita, Kansas