

15-185-12008-0000


2

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

STAFFORD County. Sec. 31 Twp. 24s Rge. 13W (#) (W)
Location as "NE/CNWxSWx" or footage from lines. NE NW SW
Lease Owner PETROLEUM, INC.
Lease Name BOWKER "H" Well No. 2
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed NOVEMBER 26 19 60
Application for plugging filed NOVEMBER 26 19 60
Application for plugging approved NOVEMBER 26 19 60
Plugging commenced NOVEMBER 26 19 60
Plugging completed NOVEMBER 26 19 60
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production: NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4377 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	259'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 250' FOLLOWED BY WOODEN PLUG AND 1/4 SACK HULLS.
PLACED 25 SACKS CEMENT THROUGH DRILL PIPE ON TO HULLS. MUDDED UP WITH HEAVY
MUD TO 35' FOLLOWED BY WOODEN PLUG, 1/2 SACK HULLS AND 10 SACKS CEMENT TO BASE
OF WELL CELLAR.

12-20-60

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 19TH day of DECEMBER, 19 60

My commission expires APRIL 14, 1963

Arthur J. White
Notary Public.



15-185-12008-0000
WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 31 T-24S R. 13W

FARM BOWKER "H" NO. 2


LOC. NE, NW, SW

TOTAL DEPTH 4377'

COUNTY STAFFORD CO., KANSAS

COMM. November 15, 1960 COMP. November 26, 1960

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 259' w/225 sax.

ELEVATION 1948' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Surface sand
190	Sand & clay
259	Shale
855	Red bed & shale
875	Anhydrite
1630	Shale & shells
1940	Shale & lime
2385	Lime & shale
3160	Shale & lime
3440	Lime & shale
3960	Lime
3985	Lime & shale
4079	Lime & chert
4191	Lime
4230	Shale & lime
4240	Chert & lime
4258	Lime
4267	Lime & chert
4377	Lime
4377	T. D.

12-20-60

CONS. ENGR. STAFFORD CO. KANSAS

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #2 BOWKER "H" well

Verne A. Morris

Subscribed and sworn to before me this 16th day of December 19 60

My Commission Expires: April 14, 1963

Arthur J. Wiles
NOTARY PUBLIC