

15-185-0110-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Bowker "G"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

SPOT LOCATION C/S/2-NW SE

SEC. 31 TWP 24 RGE. 13 (E) or (W) (W)

COUNTY Stafford

Date Well Completed 12-9-60

Plugging Commenced 1-14-84

Plugging Completed 1-24-84

LEASE OPERATOR Petroleum, Inc.

ADDRESS Box 1447, Great Bend, Kansas 67530

PHONE # (316-793-8968) OPERATORS LICENSE NO. 5238

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1 (One)

Is ACO-1 filed? _____ If not, is well log attached? No

Producing formation _____ Depth to top _____ bottom T.D. 4266'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	255'	None
				5-1/2"	4264'	2592.08'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Dumped sand to 3750' and 5 sacks cement. Shot casing at 3000', 2800', 2700', and 2600'. Pulled 80 joints of 5-1/2" casing. Allied squeezed well with 3 sacks hulls, 20 sacks gel, 50 sacks cement, 5 sacks gel, 1 sack hulls, released plug and pumped 100 sacks 60/40 Pozmix cement with 6% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Ks.
67530

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1984

SUBSCRIBED AND SWORN TO before me this 26th day of January, 1984

CONSERVATION DIVISION
Wichita, Kansas

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

My Commission expires:

WELL LOG

COMPANY **PETROLEUM, INCORPORATED**

SEC. 31 T. 24S R. 13W

FARM **BOWKER "G" NO. 1**


LOC. **C-S/2, NW, SE**

TOTAL DEPTH **4266'**

COUNTY **STAFFORD CO., KANSAS**

COMM. **September 8, 1960** COMP. **September 19, 1960**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 255' w/225 sax.
5 1/2" @ 4264' w/300 sax.**

ELEVATION **1947' DF**

PRODUCTION **Arbuckle**

FIGURES INDICATE BOTTOM OF FORMATIONS

160	Surface sand
230	Shale
255	Red bed
340	Red bed & shale
370	Anhydrite
1735	Shale & shells
1855	Lime w/shale streaks
2300	Lime
3225	Shale & lime
3570	Lime & shale
3655	Shale & lime
3940	Lime
4020	Shale & lime
4063	Shale X
4108	Shale & lime
4195	Cherty lime
4208	Lime
4258	XXXX Shale
4266	Shale & lime
4266	T. D.

RECEIVED
STATE CORPORATION COMMISSION

JAN 04 1984

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 BOWKER "G" well

Subscribed and sworn to before me this 3rd day of October 19 60

My Commission Expires: April 14, 1963

Verne A. Morris

Arthur J. Mule
NOTARY PUBLIC