

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR


SW NW NE ?

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 27 Twp. 24S Rge. (E) 13 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. Center E line of W/2 of NE $\frac{1}{4}$
Lease Owner. The Atlantic Refining Company
Lease Name. Stephen Pound Well No. 2
Office Address. P. O. Box 17 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole). Dry hole
Date well completed. September 13 19. 37
Application for plugging filed. January 31 19. 39
Application for plugging approved. January 31 19. 39
Plugging commenced. February 2 19. 39
Plugging completed. April 5 19. 39
Reason for abandonment of well or producing formation. No Production

If a producing well is abandoned, date of last production. 19.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Guy Wiershing
Producing formation. Lansing Depth to top. 3586 Bottom. 3653 Total Depth of Well. 4149 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Lansing</u>	<u>Water</u>	<u>3586</u>	<u>3653</u>	<u>13 3/8"</u>	<u>408'</u>	<u>None</u>
				<u>7"</u>	<u>4130'</u>	<u>2019'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Plugged back with cement from 4149 to 3600
Heavy mud from 3600 to 520
Plugged with rock and cement from 520 to 490
Plug and 5 sacks cement from 490 to 400
Heavy mud from 400 to 20
Cement from 20 to surface



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Atlantic Refining Company
Address P. O. Box 17 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, SS.
Stanton K. Myers (employee of owner) or (~~owner or operator~~) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanton K. Myers
P. O. Box 17 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of May, 19. 47

Commission expires Oct 28 1948
H. C. Colegrove
Notary Public.

