

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

1-9-1967

Operator's Full Name Hellar Drilling Company, Inc., & H. C. HopkinsComplete Address: 1014 Union Center Bldg., Wichita, KansasLease Name Suiter Well No. # 1Location C S/2 S/2 NW Sec. 23 Twp. 24 Rge. 13 (E) (W) WCounty Stafford Total Depth 4102'Abandoned Oil Well Gas Well Input Well SWD Well D & A X Other well as hereafter indicated: Plugging Contractor: Hellar Drilling Company, Inc.Address: 1014 Union Center Bldg., Wichita, Kansas License No. Operation Completed: Hour 2:00PM Day 7th Month Jan. Year 1967

The Above well was plugged as follows:

225' of 8 5/8" surface pipe, cement circulated with 185 sacks. Fluid level in the hole was at 60'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 200', and cemented with 25 sacks at 200', through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 1/10/67INV. NO. 4583-4