

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
MAR 9 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name Benton Well No. # 4

Location C N/2 NW SW Sec. 23 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 4119'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30PM Day 4th Month March Year 1966

The Above well was plugged as follows:

347' of 8 5/8" surface pipe, cemented with 150 sacks. 4098' of 5 1/2" long
string, cemented with 185 sacks. 3870' of 4 1/2" welded long string, cemented
with 75 sacks. Plug back TD 3804'. Top perferation 3580'. Bottom of the hole
was sanded to 3531', and cemented with 5 sacks. 828' of 4 1/2" long string was
recovered from the hole. 20' of 5 1/2" long string was recovered from the hole.
A squeeze job was necessary. 10 sacks of Gel-Mud and 80 sacks of cement was
pumped through an 8 5/8" swage in the surface pipe to a pressure of 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/9/66
INV. NO. 2837-W

Signed: Austin Claving
Well Plugging Supervisor