

96
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1965

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Woodman & Iannitti

Complete Address: 706 Union National Bldg., Wichita, Kansas

Lease Name Kim^Kpatrick Well No. # 1

Location NE NW NE Sec. 36 Twp. 24 Rge. 13 (E) (W)W

County Stafford Total Depth 4169'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Woodman & Iannitti

Address: 706 Union National Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 12:00PM Day 13th Month April Year 1965

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid
level was up in the hole. 1st cementing plug and 1/2 sack of hulls was
pushed in fluid to 230', and cemented with 25 sacks, through the drill
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/14/65
INV. NO. 986-W