

15-185-30072-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address: 801 Union Center Bldg., Wichita, Kansas

Lease Name De Busk Well No. # 1

Location C NE NE Sec. 29 Twp. 24 Rge. 14 (E) W

County Stafford Total Depth 3870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Abercrombie Drilling, Inc.

Address: 801 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 2:30 AM Day 3rd Month July Year 1965

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cement circulated with 165 sacks. Fluid
level in the hole was at 226'. 1st cementing plug and 1 sack of hulls
was pushed in fluid to 240', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-7-65

INV. NO. 1420-W