



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 - 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl Bldg Wichita, Ks

Lease Name Sparks C Well No. 1

Location SW/SW/SW Sec. 29 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 4377

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 9:00 AM Day 30 Month 6 Year 1971

The above well was plugged as follows:

277 ft 8 5/8 surface pipe cemented with 200 sacks. 4369 ft 5 1/2 long
string cemented with 125 sacks. Top perf. 4122 ft. Sand back to
4000 ft. Pulled 2218 ft 5 1/2. Fluid level 50 ft. Pumped 2 sacks hulls,
15 sacks gel., 100 sacks cement to surface. Maximum pressure 550 lbs.
Final pressure 250 lbs.

Pumped by Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: M Russell Bilsbarger
Well Plugging Supervisor

DATE 7/2/71
INV. NO. 3933-4